BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/RD/WORK_INDENT16937

NEGOTIATION SCHEDULE - B

EE/BTP/BBMP/E-PMT/11/2014-15, Date: 25.03.2015

Road Development and concrate road works at Kuvempunagar 2nd Stage Main road in ward no. 11.

Sl. No.	Approved Qty.	Description	Unit	Negotiation Tender Rates of N KEERTHI	
				In Figures	In Words
1	177	Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	105.58	
2	177	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4834.92	
3	115	Providing & fixing 20 mm thick compressible fibre board in expansion joint complete as per drawing & technical specification etc complete as per specifications and directions of engineer in charge of the work	M	137.89	
4	147.5	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregares @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5837.89	
5	1180	Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratiry, Power Floater, blade and disc etc complete as per specifications and directions of engineer in charge of the work	Sqm	96.98	
6	2.97	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastisiser @ 3lts confirming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, curing, etc complete as per specifications and directions of engineer in charge of the work	Cum	6050.12	

Sl. No.	Approved Qty.	Description	Unit	Negotiation Tender Rates of N KEERTHI	
				In Figures	In Words
7	1.78	Providing mild steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery etc complete as per specifications and directions of engineer in charge of the work	Qtl	7955.86	
8	165.18	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness above 200 mm including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	383.52	
9	177	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading etc complete as per specifications and directions of engineer in charge of the work	Cum	72.53	

N. Keerthi
Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

BRUHAT BENGALOORE MAHANARA PALIKE,YELAHANKA ZONE

BYATARAYANAPURA DIVISION

SCHEDULE-B (As Per Negotiated)

BBMP/2014-15/RD/WORK_INDENT16937

Road Development and concrate road works at Kuvempunagar 2nd Stage Main road in ward no. 11.

Sl. No.	Description	Item Code	Unit	Qty	Sanctioned Estimate		Rates Quoted Before Negotiation N KEERTHI		Rates Quoted After Negotiation N KEERTHI	
					Rate	Amount	Rate	Amount	Rate	Amount
1	Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift	1	Cum	177	105.84	18733.68	110.0	19470.00	105.58	18686.85
2	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size	2	Cum	177	4847	857926.08	5100.0	902700.00	4834.92	855781.26
3	Providing & fixing 20 mm thick compressible fibre board in expansion joint complete as per drawing & technical	3	M	115	138.24	15897.6	145.0	16675.00	137.89	15857.86
4	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300 kgs, with 20mm and down size	4	Cum	147.5	5852.5	863246.7	6000.0	885000.00	5837.89	861088.58
5	Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including	5	Sqm	1180	97.2	114696	110.0	129800.00	96.96	114409.26
6	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and	6	Cum	2.97	6065.3	18013.882	6200.0	18414.00	6050.12	17968.85
7	Providing mild steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position,	7	Qtl	1.78	7975.8	14196.924	8500.0	15130.00	7955.86	14161.43
8	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as	8	Sqm	165.18	384.48	63508.406	420.0	69375.60	383.52	63349.64
9	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading etc	9	Cum	177	72.71	12869.67	95.0	16815.00	72.53	12837.50
	Total					**1979088.94**		**2073379.60**		**1974141.22**

	N KEERTHI		N KEERTHI	
	2073379.60	-1979088.94	1974141.22	-1979088.94
Over Sanctioned Rates	94290.66	4.76%	-4947.72	-0.25%
	1979088.94		1979088.94	

The Lowest Rates Quoted by N·KEERTHI, Contractor is 0.25% Below the Sanctioned Estimate rates is recommended for kind Approval.

16/04.

Assistant Engineer
Byatarayanapura Division

Executive Engineer
Byatarayanapura Division

ರವರಿಗೆ,
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬಿಬಿಎಂಪಿ, ಬೆಂಗಳೂರು-92.

ಮಾನ್ಯರೇ,

ವಿಷಯ:- ಧರಸಂದಾನ ನಡೆಸುವ ಬಗ್ಗೆ.
ಉಲ್ಲೇಖ:- ತಮ್ಮ ಪತ್ರದ ದಿನಾಂಕ: 16/04/15

-******-

ಮೇಲ್ಕಂಡ ವಿಷಯಕ್ಕೆ ಸಂಬಂದಿಸಿದಂತೆ, ಟೆಂಡರ್ 10/14-15 ದಿನಾಂಕ: 21.02.2015ರ ಇಂಡೆಂಟ್ ಸಂಖ್ಯೆ: 16937 ಕ್ಕೆ ನನ್ನ ಧರಗಳನ್ನು ನಮೂದಿಸಿ ನಿಯಮಾನುಸಾರ ಟೆಂಡರ್ ಸಲ್ಲಿಸಿರುತ್ತೇನೆ. ನಿಮ್ಮ ಕಛೇರಿ ಪತ್ರದಂತೆ ದರ ಸಂಧಾನಕ್ಕೆ ಒಪ್ಪಿದ್ದು, ಟೆಂಡರ್‌ನಲ್ಲಿ ನಮೂದಿಸಿದ್ದ ದರಗಳಿಗಿಂತ -0.25% ಕಡಿಮೆ ದರಗಳಿಗೆ ಕಾರ್ಯ ನಿರ್ವಹಿಸಲು ಒಪ್ಪಿಸುತ್ತೇನೆ.

DM
16/4/2015

N.Narasappa.
ತಮ್ಮ ವಿಶ್ವಾಸಿ

ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

ಯಲಹಂಕ ವಲಯ ಬೆಂಗಳೂರು–92.

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ ಕಛೇರಿ
ಬೃ.ಬೆ.ಮ.ಪಾ. ಬೆಂಗಳೂರು–92.

ದೂರವಾಣಿ: 23636671

ಸಂಖ್ಯೆ: ಬೃ.ಬೆ.ಮ.ಪಾ/ಬ್ಯಾ.ವಿ/ಕಾ.ಅ/T-10/2015–16
16937

ದಿನಾಂಕ: 16/04/2015

ರವರಿಗೆ,

N. Keerthi
#66, Anandappa building
Hospital road, Yelahanka
Bangalore-64.

ಮಾನ್ಯರೇ,

ವಿಷಯ:– Road Development and concrate road works at Kuvempunagar 2nd Stage Main road in ward no. 11
ಕಾಮಗಾರಿಗೆ ದರಸಂದಾನಕ್ಕೆ ಆಹ್ವಾನಿಸುವ ಬಗ್ಗೆ.

ಗುತ್ತಿಗೆದಾರರಾದ ತಾವು ಇ–ಪ್ರಕ್ಯೂರ್‌ಮೆಂಟ್ ಟೆಂಡರ್ ಸಂಖ್ಯೆ: **10/14-15, ದಿ: 21.02.2015**ರ ಇಂಡೆಂಟ್ ಸಂಖ್ಯೆ: 16937 ಭಾಗವಹಿಸಿದ್ದು, ನೀವು ಏಕೈಕ ಗುತ್ತಿಗೆದಾರರಾಗಿರುತ್ತೀರಿ. ಆದ್ದರಿಂದ ಸದರಿ ಕಾಮಗಾರಿಯನ್ನು ನಿರ್ವಹಿಸಲು ತಮ್ಮನ್ನು ದರಸಂದಾನಕ್ಕೆ ಆಹ್ವಾನಿಸುತ್ತಾ, ಈ ಪತ್ರ ತಲುಪಿದ 3 ದಿನಗಳೊಳಗಾಗಿ ದರಸಂದಾನ ದರಗಳನ್ನು ಸಲ್ಲಿಸಲು ಸೂಚಿಸಿದೆ. ಇಲ್ಲವಾದಲ್ಲಿ ನಿಮ್ಮ ಟೆಂಡರ್‌ನ್ನು ರದ್ದುಪಡಿಸಿ ಮರುಟೆಂಡರ್ ಕರೆಯಲಾಗುವುದು ಈ ಬಗ್ಗೆ ಇನ್ನು ಮುಂದೆ ಯಾವುದೇ ತಿಳುವಳಿಕೆ ಪತ್ರಗಳನ್ನು ನೀಡಲಾಗುವುದಿಲ್ಲ.

ತಮ್ಮ ವಿಶ್ವಾಸಿ,

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬಿಬಿಎಂಪಿ, ಬೆಂಗಳೂರು–92.